



Guideline For

Project Milestones and Deliverables

Week 1

- ☐ Client Contact (Phone and Email).
- ☐ Project set up complete within Procore.
- ☐ Schedule review.
- ☐ Specification review.
- ☐ Scope/Estimating Budget Review.
- ☐ Buyout (Solidify Scope, Cost then Release ALL shop drawings).
- ☐ Issue LOI's as scope buyout progresses
- ☐ Submittal Requests (all product data, test reports, O&M's, physical samples, warranties, etc.) Physical samples request min of (4) but also per specifications.

Week 2

- ☐ Develop Milestone Schedule (Within 2 weeks of turnover). Smart Sheet is a great tool for this.
- ☐ Create Submittal Log and send copy to the client for review.
- ☐ You should have received a lot of the electronic submittals by now so you can populate the submittal while creating the log.
- ☐ Work on PM material budget as items come in and get worked out.
- ☐ Complete schedule of values and send to the client for review and approval.

Week 3-4

- ☐ Continue client contact.
- ☐ Continue contract drawing review (reviewing details in depth.)
- ☐ Manage building schedule and adjust and apply pressure where needed if needed.
- ☐ Continue to manage submittals and submittal log.
- ☐ Submit any RFI's gathered during review.
- ☐ Send drafter specifics for the drawings for what you want them to include. (glass types, column line dimensions, what items are not by 1CG, what items are by 1CG, what items are by the manufacturer, show dimensions in feet or inches, etc)
- ☐ Work on PM material budget as items come in and get worked out.
- ☐ Review submittal items that have come in. Log them and submit as they come in **if the project schedule doesn't allow for a complete submittal package at one time.**
- ☐ Set up scheduled date for an internal "project approach meeting". Include VP of construction, VP of operations, Safety coordinator, General superintendent, installer if determined, shop manager, estimator and whomever else that you feel is required. This step will vary depending on project level. **Use your best assumption on If this is a requirement for the specific project or not.**
- ☐ Review and start putting together required information for the internal project approach meeting. Review the 1CG "project approach guideline" for assistance with preparation.
- ☐ Project billings as applicable.

Week 5

- ☐ Continue client contact.
- ☐ Continue contract drawing review (reviewing details in depth).
- ☐ Manage building schedule and adjust and apply pressure where needed if needed.
- ☐ Continue to manage submittals and submittal log.
- ☐ Work on PM material budget as items come in and get worked out.
- ☐ All physical samples should be in by now. Review for accuracy, clean and label each sample with our 1CG labels. Reach out to client to find out where they want the physical samples to go. Box them up and get with 1CG admin to get them sent out.
- ☐ Perform the internal “**project approach meeting**”. Make sure accurate detailed notes are taken.
- ☐ Send out any notes from discussions to the entire team to ensure everyone is on the same page.
- ☐ If anything from this discussion affects the shop drawings be sure to send those out to the drafter so they can be incorporated.

Week 6-8

- ☐ Continue client contact.
- ☐ Continue contract drawing review (reviewing details in depth).
- ☐ Manage building schedule and adjust and apply pressure where needed if needed.
- ☐ Continue to manage submittals and submittal log.
- ☐ You should be able to submit all items excluding shop drawings at this point.
- ☐ Receive 1st submission shops, review and send out for internal **constructability review**. Refer to the constructability review guideline for this.
- ☐ Revise shop drawings to reflect any comments from reviews.
- ☐ Send over any notes to the GC (if any) that require attention from these reviews to start conversations on the path forward.

Week 8-10

- ☐ Prepare all scope items for the project **AND** turn over to operations for their budget. This turnover should be formal in person to go over the project and any specifics regarding scope and pricing. Refer to the “**Internal Operations Budget Turnover Guideline**” (Completed scope sheet, highlighted arc's, shop drawings, scope of work from the contract, etc for a complete package. They will provide budgets for installation, fabrication, equipment and anything else that pertains to them. (operations are allowed a 2-week turnaround for this)
- ☐ Continue client contact.
- ☐ Continue contract drawing review (reviewing details in depth).
- ☐ Manage building schedule and adjust and apply pressure where needed if needed.
- ☐ Continue to manage submittals and submittal log.
- ☐ Submit shop drawings if not already submitted.
- ☐ Submit any remaining submittals.
- ☐ Turn in PM final budget that includes operations budget numbers to your department head.

- ☐ Project billings as applicable.

Pre-Material release

- ☐ Shop drawings approved
- ☐ Finish selection approved
- ☐ Product data approved
- ☐ Physical samples approved
- ☐ Door hardware schedule and cut sheets approved
- ☐ Sequence plan sent to the metal vendor to ensure proper material optimization

Premobilization

- ☐ Continue communications with client and internally to ensure the project approach is still on track as planned.
- ☐ Upon receipt of F&F shops the PM is to present on the project to Field and Fabrication team. Reference the **"field and Fab turnover guideline"** for items to include in this review.
- ☐ Confirm engineering is completed and incorporated into the field and file shops as applicable.
- ☐ Order Installation and fabrication supplies required. Make sure to collaborate with the team to ensure everything is captured.
- ☐ Complete Site Readiness inspections
- ☐ Confirm all safety documents, background checks etc. are completed and submitted as applicable.
- ☐ Confirm internally that the team is on the same page for deliveries and with the frame construction minding the weight and sizes.
- ☐ Confirm equipment is set up and ready to go.
- ☐ Confirm laydown are with client.

Mobilization

- ☐ Project manager, General Superintendent, Safety manager and quality control manager required to be onsite for initial mobilization.
- ☐ Get through onsite orientation as required by the client.
- ☐ Review layout items to ensure all control lines, benchmarks etc are established and confirm what they represent in the building.
- ☐ Go over the starting point and sequence **again** with the onsite Forman and general contractor to ensure everyone is on the same page.
- ☐ Review initial installation with the field team and walk through all steps if possible, to ensure the installation is per installation instructions, meets 1CG expectations and the projects intent. 1CGF quality control manager to be engaged in this process.

50%-60% Completion

- ☐ Continue client contact.

- ☐ Continue contract drawing review (reviewing details in depth.)
- ☐ Manage building schedule and adjust and apply pressure where needed if needed.
- ☐ Review the project's completed and remaining scope for comparison with the PM's takeoff and allocated dollars to the budget to ensure accuracy and make any adjustments to the budget necessary for it to be accurate.
- ☐ Pre-Punch
- ☐ Request retain reduction from the client.

80% Completion

- ☐ Continue client contact.
- ☐ Continue contract drawing review (reviewing details in depth.)
- ☐ Manage building schedule and adjust and apply pressure where needed if needed.
- ☐ Review the project's completed and remaining scope for comparison with the PM's takeoff and allocated dollars to the budget to ensure accuracy and make any adjustments to the budget necessary for it to be accurate.
- ☐ Pre-Punch
- ☐ Start putting together an exit plan for the project. Reviewing any and all possible loose ends to get ahead of the completion of the project.

90 - 95% Completion

- ☐ Continue client contact.
- ☐ Continue contract drawing review (reviewing details in depth.)
- ☐ Manage building schedule and adjust and apply pressure where needed if needed.
- ☐ Review the project's completed and remaining scope for comparison with the PM's takeoff and allocated dollars to the budget to ensure accuracy and make any adjustments to the budget necessary for it to be accurate.
- ☐ Pre-Punch
- ☐ Confirm the items on the previous exit plan were completed and continue walking the project and adding items as you see fit.
- ☐ Request retain reduction from the client.

95-100% Completion

- ☐ Continue client contact.
- ☐ Continue contract drawing review (reviewing details in depth.)
- ☐ Manage building schedule and adjust and apply pressure where needed if needed.
- ☐ Review the project's completed and remaining scope for comparison with the PM's takeoff and allocated dollars to the budget to ensure accuracy and make any adjustments to the budget necessary for it to be accurate.
- ☐ Confirm the items on the previous exit plan were completed and continue walking the project and adding items as you see fit to ensure the project is up to 1CG standards.
- ☐ Review and complete the punch list provided by the client
- ☐ Review and complete the punch list provided by the Owner and Architect.
- ☐ Review project specifications for a refresher on close out documents.

- ☐ Start putting together all project close outs documentation as required per project specifications. (Follow "Project Closeout Process Procore" document.)
- ☐ Once the substantial completion date is received request all remaining close outs which should be the project specific warranties.
- ☐ Bill the project out 100%.

After Completion

- ☐ Bill retain 100%

